


Plywood Lay-up Line R3

设计巧妙且经济实惠的组坯线



胶合板组坯线 R3 - 具有成本效益，可满足您的所有需求

劳特胶合板组坯线 R3 是一种装机功率需求很低的组坯线。单面液体淋胶施胶法 (LEG) 比传统的滚筒施胶减少高达 20% 的胶水消耗。其操作轻柔，不会损坏较薄的板材。

成对层数使您能够在胶合板结构内使用较厚板材，降低施胶需求，从而减少胶水消耗。该生产线能够生产不均匀和均匀的层板结构。

该生产线采用自动进料，由操作工处理好单板的对齐。该生产线通常配备三个操作工，很容易维护。

20 多年来，劳特交付了世界上最多的单面胶合组坯线，利用我们的专业知识，还可以针对您的特定需求量身定制组坯线！

主要优势

7200

每 8 小时工作班次最多可
生产 7500 张单板

-20%

节省胶水消耗达 20%



适合您最终产品需求的成对
层数



装机功率需求低



图像和视频


BENEFITS OF ONE-SIDED GLUING

-25% One-sided gluing saves up to 25% in glue consumption compared to traditional roller gluing.



IMPROVED OVERALL QUALITY

No mechanical contact with glue application, ensuring the risk of leakage, especially on long and thin boards. Reduced manual board handling. Easy board control. Better thickness variation and wood glue use for same glue amount, making the use of glue more efficient.



The machines are automatically washed regularly for a better work environment and lower maintenance needs. The reduction in chemical use makes the process and end product more environmentally and cost-effective.

RAUTE VIDEO

RS SERIES NEW KID ON THE BLOCK

EMO KS

RAUTE VIDEO

PLYWOOD LAY-UP LINE R3

EMO

RAUTE VIDEO

COST-EFFICIENT FOR ALL YOUR NEEDS

EMO PLYWOOD LAY-UP LINE R3

技术规格

生产线上的操作工	3
施胶方法	液体挤出机
混合单板进给	●
胶合板尺寸	4x8, 5x5
最高产能（面板/8 小时）	7200